



The contractor is responsible for the verification of dimensions on the site.  
All dimensions are in millimetres. © Copyright all rights reserved South Tyneside Council.  
Ordnance Survey data has been reproduced from Mastermap with the permission of The Controller of  
H.M. Stationery Office. Crown copyright reserved.Licence No.100019570

**KEY**

- FOOTWAY WORKS: 63m2
- CARRIAGEWAY RESURFACE: 105m2
- UNCONTROLLED CROSSING (BUFF TACTILES)
- NEW CARRIAGEWAY (FULL CONS.): 33m2
- FOOTWAY HARDENED: 8.3m2
- OLD KERBLINE TO REMOVE: 21m
- OLD KERBLINE TO LIFT AND RELAY: 22.1m
- NEW KERBLINE TO INSTALL: 21.2m
- NEW PEDESTRIAN GUARDRAIL TO INSTALL: 26m
- WHITE ROAD MARKINGS
- PROPOSED NO WAITING NO LOADING AT ANY TIME
- BOLLARDS TO REMOVE: 5 no.
- BOLLARDS TO REMAIN
- POST AND SIGN TO INSTALL: 2 no.

Rev	Date	Description	Chkd
-----	------	-------------	------



# South Tyneside Council

## Regeneration and Environment

Town Hall & Civic Offices, Westoe Road, South Shields, Tyne & Wear, NE33 2RL  
Telephone: (0191) 427 1717    Fax: (0191) 455 7770

Project

# Highfield Road, South Shields

Drawing Title

# Concept Design

Drawn by	HB	Date	25/03/25
Checked by	SV	Date	25/02/25
Scale	NTS	Size	A3

Project Code	Drawing Number
TRS12-BUS-2025	01-1